DOOR SCHEDULE

DOOR NUMBER	LOCATION (TO/FROM)	SIZE	DOOR TYPE	DOOR MATERIAL	DOOR FINISH	FRAME TYPE	FRAME MATERIAL	FRAME FINISH	HARDWARE	HANDICAP ACCESS	COMMENTS
B01	LAUNDRY ROOM/CORRIDOR	914mm x 2032mm x 38mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 10	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
B02	B02 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
B02A	WASHROOM/B02 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
B02B	EXTERIOR/B02 STUDIO UNIT	2133mm x 2032mm	D-07	GLAZ/ ALUM	–	–	ALUM	–		–	
B03	B03 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
B03A	WASHROOM/B03 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
B03B	EXTERIOR/B03 STUDIO UNIT	2133mm x 2032mm	D-07	GLAZ/ ALUM	–	–	ALUM	–		–	
B04	B04 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
B04A	WASHROOM/B04 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
B04B	EXTERIOR/B04 STUDIO UNIT	2133mm x 2032mm	D-07	GLAZ/ ALUM	–	–	ALUM	–		–	
B05	B05 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
B05A	WASHROOM/B05 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
B05B	EXTERIOR/B05 STUDIO UNIT	2133mm x 2032mm	D-07	GLAZ/ ALUM	–	–	ALUM	–		–	
B06	B06 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
B06A	WASHROOM/B06 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
B06B	EXTERIOR/B06 STUDIO UNIT	2133mm x 2032mm	D-07	GLAZ/ ALUM	–	–	ALUM	–		–	
B07	LINEN ROOM/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 05	–	F.R.R. RATING OF 90 MINUTES FOR BOTH DOOR AND FRAME
B08	NEW HAIR SALON/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 05	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
B09	MULTIPURPOSE ROOM/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 10	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
B10	ELEVATOR MACHINE ROOM/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 06	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
B11	GARBAGE ROOM/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 06	–	F.R.R. RATING OF 90 MINUTES FOR BOTH DOOR AND FRAME
B12	CORRIDOR/BOILER ROOM	914_384mm x 2032mm x 44mm	D-10	STEEL	PAINT	F-05	STEEL	PAINT	GROUP 05B	–	F.R.R. RATING OF 90 MINUTES FOR BOTH DOOR AND FRAME
B12A	WATER ENTRY ROOM/BOILER ROOM	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 06	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
B12B	ELECTRICAL ROOM/BOILER ROOM	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 06	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
B13	NEW DATA ROOM/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 05	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
SB01	EAST STAIRCASE/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 03		F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
SB02	WEST STAIRCASE/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 03	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
BC01	JAN./CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 05	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
BC02	CORRIDOR/CORRIDOR	914_384mm x 2032mm x 44mm	D-10	STEEL	PAINT	F-05	STEEL	PAINT	GROUP 05	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
G01	G01 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
G01A	WASHROOM/G01 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
G01B	EXTERIOR/G01 STUDIO UNIT	2133mm x 2032mm	D-07	GLAZ/ ALUM	–	–	ALUM	–		–	
G02	G02 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
G02A	WASHROOM/G02 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
G02B	EXTERIOR/G01 STUDIO UNIT	2133mm x 2032mm	D-07	GLAZ/ ALUM	–	–	ALUM	–		–	
G03	G03 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
G03A	WASHROOM/G03 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
G03B	EXTERIOR/G03 STUDIO UNIT	2133mm x 2032mm	D-07	GLAZ/ ALUM	–	–	ALUM	–		–	
G04	WASHROOM G04/CORRIDOR	914mm x 2032mm x 44mm	D-06	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 12	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
G05	WASHROOM G05/CORRIDOR	914mm x 2032mm x 44mm	D-06	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 12	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
G06	NEW ACTIVITY ROOM/CORRIDOR	2-914mm x 2032mm	D-08	GLAZ/ ALUM	–	–	ALUM	–	GROUP 14	YES	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
G06A	EXTERIOR/NEW ACTIVITY ROOM	914mm x 2032mm	D-09	GLAZ/ ALUM	–	–	ALUM	–	GROUP 15	–	
G07	KIM'S OFFICE/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 05	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
G08	HENRI'S OFFICE/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 05	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
SG01	EXTERIOR/EAST STAIRCASE	914mm x 2032mm	D-09	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 05A	–	
SG02	EAST STAIRCASE/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 03	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
SG03	WEST STAIRCASE/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 03	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
SG04	EXTERIOR/WEST STAIRCASE	914mm x 2032mm	D-09	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 05A	–	
GC01	CORRIDOR/NEW COMMON LIVING RM	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 02	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
GC02	COMMON LIVING RM/NEW TERRACE	2-914mm x 2032mm	D-08	GLAZ/ ALUM	–	–	ALUM	–	GROUP 15	–	
GC03	LINEN CHUTE/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 10	–	F.R.R. RATING OF 90 MINUTES FOR BOTH DOOR AND FRAME
GC04	GARBAGE CHUTE/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 10	–	F.R.R. RATING OF 90 MINUTES FOR BOTH DOOR AND FRAME
GC06	EXTERIOR/NEW ENTRANCE VESTIBULE	2-914mm x 2032mm	D-08	GLAZ/ ALUM	–	–	ALUM	–	GROUP 15	YES	
GC07	NEW ENTRANCE VESTIBULE/EXISTING BLDG.	2-914mm x 2032mm	D-08	GLAZ/ ALUM	–	–	ALUM	–	GROUP 15	YES	F.R.R. RATING OF 0-MINUTES FOR BOTH DOOR AND FRAME. DOOR TO BE ON HOLD OPEN SYSTEM.
GC08	CORRIDOR/EXISTING BLDG.	2-914mm x 2032mm	D-08	GLAZ/ ALUM	–	–	ALUM	–	GROUP 15	YES	
GC09	COURTYARD/CORRIDOR	2-914mm x 2032mm	D-08	GLAZ/ ALUM	–	–	ALUM	–	GROUP 15	YES	
201	201 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01		F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
201A	WASHROOM/201 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
202	202 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
202A	WASHROOM/202 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
203	203 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
203A	WASHROOM/203 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
204	204 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
204A	WASHROOM/204 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
205	205 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
205A	WASHROOM/205 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
206	206 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
206A	WASHROOM/206 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
207	207 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
207A	WASHROOM/207 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	

DOOR NUMBER	LOCATION (TO/FROM)	SIZE WxH	DOOR TYPE	DOOR MATERIAL	DOOR FINISH	FRAME TYPE	FRAME MATERIAL	FRAME FINISH	HARDWARE	HANDICAP ACCESS	COMMENTS
208	208 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
208A	WASHROOM/208 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
209	209 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
209A	WASHROOM/209 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
210	210 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
210A	WASHROOM/210 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
S201	EAST STAIRCASE/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 03	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
S202	WEST STAIRCASE/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 03	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
2C01	LINEN CHUTE/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 10	–	F.R.R. RATING OF 90 MINUTES FOR BOTH DOOR AND FRAME
2C02	GARBAGE CHUTE/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 10	–	F.R.R. RATING OF 90 MINUTES FOR BOTH DOOR AND FRAME
2C03	CORRIDOR/ELEC. CLOSET	712mm x 2032mm x 44mm	D-05	STEEL	PAINT	F-04	STEEL	PAINT	GROUP 07	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
301	301 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
301A	WASHROOM/301 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
302	302 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
302A	WASHROOM/302 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
303	303 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
303A	WASHROOM/303 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
304	304 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
304A	WASHROOM/304 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
305	305 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
305A	WASHROOM/305 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
306	306 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
306A	WASHROOM/206 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
307	307 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
307A	WASHROOM/307 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
308	308 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
308A	WASHROOM/308 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
309	309 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
309A	WASHROOM/309 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
310	310 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
310A	WASHROOM/310 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
S301	EAST STAIRCASE/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 03	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
S302	WEST STAIRCASE/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 03	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
3C01	LINEN CHUTE/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 10	–	F.R.R. RATING OF 90 MINUTES FOR BOTH DOOR AND FRAME
3C02	GARBAGE CHUTE/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 10	–	F.R.R. RATING OF 90 MINUTES FOR BOTH DOOR AND FRAME
3C03	CORRIDOR/ELEC. CLOSET	712mm x 2032mm x 44mm	D-05	STEEL	PAINT	F-04	STEEL	PAINT	GROUP 07	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
401	401 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
401A	WASHROOM/401 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
402	402 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
402A	WASHROOM/402 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
403	403 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
403A	WASHROOM/403 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
404	404 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
404A	WASHROOM/404 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
405	405 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
405A	WASHROOM/405 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
406	406 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
406A	WASHROOM/406 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
407	407 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
407A	WASHROOM/407 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
408	408 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
408A	WASHROOM/408 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
409	409 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
409A	WASHROOM/409 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
410	410 STUDIO UNIT/CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 20 MINUTES FOR BOTH DOOR AND FRAME
410A	WASHROOM/410 STUDIO UNIT	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	
S401	EAST STAIRCASE/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 03	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
S402	WEST STAIRCASE/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 03	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
4C01	LINEN CHUTE/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 10	–	F.R.R. RATING OF 90 MINUTES FOR BOTH DOOR AND FRAME
4C02	GARBAGE CHUTE/CORRIDOR	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 10	–	F.R.R. RATING OF 90 MINUTES FOR BOTH DOOR AND FRAME
4C03	CORRIDOR/ELEC. CLOSET	712mm x 2032mm x 44mm	D-05	STEEL	PAINT	F-04	STEEL	PAINT	GROUP 07	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
EBB1	NEW ELECTRICAL ROOM /EXISTING STORAGE ROOM	914mm x 2032mm x 44mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 06	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
EBG1	EXISTING BEDROOM/LOBBY	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	
EBG2	EXISTING BEDROOM/LOBBY	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
EBG3	EXISTING BEDROOM/LOBBY	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
EBG5	NEW RECEPTION/CORRIDOR	914mm x 2032mm x 38mm	D-02	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 05	–	
EBG6	LOBBY/CORRIDOR	914mm x 2032mm x 38mm	D-03	STEEL	PAINT	F-01	STEEL	PAINT	GROUP 03	–	F.R.R. RATING OF 0-MINUTES FOR BOTH DOOR AND FRAME. DOOR TO BE ON HOLD OPEN SYSTEM.
EBG7	DR'S OFFICE/NURSE OFFICE	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 10	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME. COORDINATE KEYING WITH NURSE STATION
EBG8	EXISTING KITCHEN/EXISTING OFFICE	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 10	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
EBG9	EXISTING OFFICE/DINING AREA	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 10	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
EBS1	EXISTING BEDROOM/EXISTING CORRIDOR	914mm x 2032mm x 44mm	D-01	WOOD	PAINT	F-01	STEEL	PAINT	GROUP 01	–	F.R.R. RATING OF 45 MINUTES FOR BOTH DOOR AND FRAME
EBS2	BATHROOM/EXISTING BEDROOM	914mm x 2032mm x 38mm	D-02	WOOD	STAIN	F-03	WOOD	PAINT	GROUP 12	–	

1 SC.01 DOOR SCHEDULE N.T.S.

NOTE:
COORDINATE ALL FINISHESAND COLORS WHIT INTERIOR DESIGN PACKAGE

HARDWARE NOTES

GROUP 01
- 1-1/2 PAIR OF BALL BEARINGS HINGES
- 1 MORTISE LOCKSET C/W LEVER ACTION, DEAD BOLT & ESCUTCHEON
- 1 DOOR CLOSURE
- 1 FLOOR MOUNTED DOOR STOP
- 1 KICK PLATE
- 1 PEEP HOLE

* ULC LABEL AS PER DOOR

GROUP 03
- 1-1/2 PAIR OF HINGES
- 1 PANIC BAR MORTISED
- 1 PULL HANDLE C/W THUMB PIECE
- 1 DOOR CLOSER
- 1 FLOOR MOUNTED DOOR STOP
- 1 KICK PLATE

* ULC LABEL AS PER DOOR

GROUP 05
- 1-1/2 PAIR OF HINGES
- 1 DOOR KNOB & KEY SET
- 1 DOOR CLOSURE
- 1 FLOOR MOUNTED DOOR STOP
- 1 KICK PLATE
- PROVIDE WEATHER STRIPPING

* ULC LABEL AS PER DOOR

GROUP 5A
- 1-1/2 PAIR OF HINGES
- 1 DOOR KNOB & KEY SET
- EXIT DEVICE C/W PANIC PUSH BAR
- 1 DOOR CLOSURE
- 1 KICK PLATE
- PROVIDE WEATHER STRIPPING

* ULC LABEL AS PER DOOR

GROUP 5B
- 3 PAIR OF HINGES
- 1 DOOR KNOB (ACTIVE LEAF)
- 1 DUMMY SET DOOR KNOB/HANDLE
- 2 FLUSH BOLTS (TOP & BOTTOM)
- 1 DOOR CLOSURE
- 2 FLOOR MOUNTED DOOR STOP
- 2 KICK PLATE

* ULC LABEL AS PER DOOR

GROUP 06
- 1-1/2 PAIR OF HINGES
- 1 DOOR KNOB & KEY SET
- 1 DOOR CLOSURE
- 1 FLOOR MOUNTED DOOR STOP
- 1 KICK PLATE

* ULC LABEL AS PER DOOR

GROUP 07
- 1-1/2 PAIR OF HINGES
- 1 DOOR KNOB & PASSAGE LOCKSET
- 1 WALL MOUNTED DOOR STOP

GROUP 10
- 1-1/2 PAIR OF HINGES
- 1 DOOR LEVER HANDLE & KEY SET
- 1 DOOR CLOSURE
- 1 FLOOR MOUNTED DOOR STOP
- 1 KICK PLATE

* ULC LABEL AS PER DOOR

GROUP 12
- 1-1/2 PAIR OF HINGES
- 1 DOOR LEVER HANDLE
- 1 PRIVACY LOCKSET
- 1 FLOOR MOUNTED DOOR STOP

GROUP 14
- 3 PAIR OF HINGES
- 2 LEVER HANDLES
- 2 DOOR CLOSURE
- 2 FLOOR MOUNTED DOOR STOP
- 2 KICK PLATE

* ULC LABEL AS PER DOOR

GROUP 15
- 3 PAIR OF HINGES
- 2 DOOR KNOB & STRIKE
- 2 DOOR CLOSURE
- 2 FLOOR MOUNTED DOOR STOP
- 2 KICK PLATE
- PROVIDE WEATHER STRIPPING

* ULC LABEL AS PER DOOR

ALL DOORS TO SUITES TO BE RATED 20 Min.

ALL CONTRACTORS TO VERIFY ALL DIMENSIONS ON SITE AND TO REPORT ALL ERRORS AND/OR OMISSIONS TO THE ARCHITECT.

ALL CONTRACTORS MUST COMPLY WITH ALL CODES AND BYLAWS AND OTHER AUTHORITIES HAVING JURISDICTION OVER THE WORK.

DO NOT SCALE DRAWINGS.

THIS DRAWING MAY NOT BE USED FOR CONSTRUCTION UNTIL SIGNED BY THE ARCHITECT.

COPYRIGHT RESERVED.

ONTARIO ASSOCIATION OF ARCHITECTS
R.J. WOODMAN
LICENCE
2425

NO.	REVISION	MM/DD/YY DATE
19		
18		
17		
16		
15		
14		
13		
12		
11		
10		
09		
08	RE-ISSUED FOR CONSTRUCTION	08/12/15
07	ISSUED FOR CONSTRUCTION	19/11/15
06	ISSUED FOR FINAL COORDINATION	13/11/15
05	ISSUED FOR COST CONSULTANT REVIEW	14/09/15
04	ISSUED FOR TENDER	05/08/15
03	ISSUED FOR COORDINATION	04/06/15
02	ISSUED FOR COORDINATION	11/02/15
01	ISSUED FOR BUILDING PERMIT	12/23/14

WOODMAN ARCHITECT & ASSOCIATES LTD.
4 BEECHWOOD, SUITE 201, OTTAWA, ONTARIO, CANADA K1L 8L9
TEL:613 228 9850 FAX:613 228 9848 mailbox@woodmanarchitect.com

CONSULTANTS:
STRUCTURAL – WSP
MECHANICAL – BGA
ELECTRICAL – BGA

PROJECT
LONG SAULT VILLA PROPOSED NEW LINKED BUILDING

DRAWING:
DOOR SCHEDULE

DATE	DECEMBER 23 2014	JOB NO.	1428
SCALE	N.T.S.	DRAWING NO.	SC.01
DRAWN BY	P.E.		
REVIEWED BY	R.J.W.		