



Long Sault Villa
53 Long Sault Drive, Long Sault, ON

TAL-CO Building Innovations
1341-2 Coker Street
Greely, Ontario K4P 1A1
Tel: 613-821-3959
Fax: 613-821-2938

Issue date: June 12/15
Rev. Date: N/A
Revision #: N/A

ADDENDUM #4 - NOTIFICATION

The following modifications and clarifications are to be accounted for when tendering on this potential contract. As well, when entering into the Form of Agreement to do the work, they shall become a part thereof.

Instruction/Clarifications:

1. **Please refer to attached Addendum #4 (2 pages).**
2. **Reminder** that all Scopes of Work listed as Tender Lot #1 (refer to Addendum #3) will be closing on Tuesday June 16, 2015 at 2:00PM.

Receipt of this addendum shall be acknowledged when submitting your tender submission. Failure to do so may result in the rejection of your Tender submission.

For questions or further information, please contact the office by e-mail at info@tal-co.com.

End of Addendum Notification No. 4



Long Sault Villa Addendum #4 - Details

TAL-CO Building Innovations Limited
1341-2 Coker Street
Greely, Ontario K4P 1A1
Tel: 613-821-3959
Fax: 613-821-2938

Issue date: June 12/15
Revision date: N/A
Revision #: N/A

Please find below the consultants response to recently reviewed questions from our sub-trades.

1. Structural Drawings refer to the Masonry Reinforcing Schedule. Please advise where we can find this Schedule.
 - **Please refer to attached schedule for Masonry Reinforcing Details, as issued by WSP on June 11, 2015.**

End of Addendum No. 4

**MASONRY WALL REINFORCING SCHEDULE
FOR SITES WITH SEISMIC HAZARD INDEX**

$0.35 < I_e \times F_a \times S_a (0.20) < 0.75$

UNLESS NOTED OTHERWISE ON PLAN, ALL MASONRY
WALLS SHALL BE REINFORCED AS FOLLOWS:

<u>MASONRY WALL REINFORCING SCHEDULE</u>		
NON-LOAD BEARING WALLS: (INCLUDES INFILL WALLS)		
WALL SIZE	HORIZONTAL REINF.	VERTICAL REINF.
4" (90mm)	N/A	N/A
6" (140mm)	STANDARD BLOCK-TRUSS (9GA.) @ 16" (400) o/c	1-15M @ 48" o/c + DWLS, SEE NOTES
8" (190mm)	STANDARD BLOCK-TRUSS (9GA.) @ 16" (400) o/c	1-20M @ 48" o/c + DWLS, SEE NOTES
10" (240mm)	HEAVY DUTY BLOCK-TRUSS (6GA.) @ 16" (400) o/c	1-20M @ 48" o/c + DWLS, SEE NOTES
12" (290mm)	HEAVY DUTY BLOCK-TRUSS (6GA.) @ 16" (400) o/c	2-15M @ 48" o/c + DWLS, SEE NOTES
<u>MASONRY WALL REINFORCING SCHEDULE</u>		
LOAD BEARING WALLS: (INCLUDES ELEVATOR SHAFTS & STAIRCASES)		
WALL SIZE	HORIZONTAL REINF.	VERTICAL REINF.
4" (90mm)	N/A	N/A
6" (140mm)	HEAVY DUTY BLOCK-TRUSS (6GA.) @ 16" (400) o/c	1-15M @ 32" o/c + DWLS, SEE NOTES
8" (190mm)	HEAVY DUTY BLOCK-TRUSS (6GA.) @ 16" (400) o/c	1-20M @ 32" o/c + DWLS, SEE NOTES
10" (240mm)	HEAVY DUTY BLOCK-TRUSS (6GA.) @ 16" (400) o/c	2-15M @ 32" o/c + DWLS, SEE NOTES
12" (290mm)	HEAVY DUTY BLOCK-TRUSS (6GA.) @ 16" (400) o/c	2-15M @ 32" o/c + DWLS, SEE NOTES