



Long Sault Villa

TAL-CO Building Innovations
1341-2 Coker Street
Greely, Ontario K4P 1A1
Tel: 613-821-3959
Fax: 613-821-2938

Issue date: June 29
Revision date: N/A
Revision #: N/A

POST TENDER ADDENDUM #2

The following modifications and clarifications are to be accounted for when tendering on this potential contract. As well, when entering into the Form of Agreement to do the work, they shall become a part thereof.

Instruction/Clarifications:

1. Drawing S2 shows the elevator walls on the ground floor level as Standard 190 Masonry Block whereas detail 1-S7 shows them as ICF.

THE SECTION 1/S7 IS CORRECT. WE WANT CONCRETE UP TO THE SECOND FLOOR AND MASONRY ABOVE THAT. CONCRETE CAN BE ICF, HOWEVER THE INSULATION WILL HAVE TO BE REMOVED FROM INSIDE THE SHAFT.

- R. GILLARD, WSP

REMINDER that all pricing revisions and/or confirmations are required by end of day June 30, 2015.

For further information, please contact e-mail at info@tal-co.com.

End of Post Tender Addendum No. 2