



B&GCO Prince of Wales
 1463 Prince of Wales Drive
 Ottawa, Ontario

Date: 14-Nov-17
 Rev. #: 2
 Rev. Date: 14-Mar-18

CONCRETE FORMWORK SCOPE OF WORK

SPECIFIC SCOPE OF WORK SUMMARY TO BE INCLUDED IN YOUR PRICE:

You must include in your quotation the work mentioned on the following pages, which is not necessarily indicated within the tender documents. All information contained within this document will form an integral component of this discipline's project contractual obligations.

Section #1 List of tender documents applicable to this request

- a) Refer to the "TENDER DOCUMENT SUMMARY" as attached.
- b) SPECIFICATIONS shall refer to all listed specifications from the various disciplines as detailed in the TENDER DOCUMENT SUMMARY found in Appendix A.
- c) DRAWINGS shall refer to all listed drawings from the various disciplines as detailed in the TENDER DOCUMENT SUMMARY found in Appendix A.

Sub-trade Estimators Input	
Rec'd	Comment

Section #2 Schedule

The specific schedule for your discipline will be distributed upon award of contract. The following information is an extract of the attached Preliminary Schedule dated TBD, which is a general guideline of our construction intentions for this project.

--	--

The specific schedule for your discipline is as follows:

Award of subcontract: 2018-03-14
 Your work must start: 2018-04-19
 Your work must finish: 2018-05-04

Section #3 General Project Scope of Work Items

- a) All Concrete Formwork required at the Boys and Girls Club Prince of Wales in reference to the Specification, including, but not limited to,

--	--
- b) Complete this scope of work according to the attached schedule, specifically within the indicated commencement and completion dates.

--	--
- c) Supply all labour, material & equipment to complete your scope of work as outlined/specified by the tender documentation and this detailed scope of work.

--	--
- d) Enforce any precautionary measures required to ensure your work is safe and protected.

--	--
- e) Provide the proper amount of qualified personnel to manage your scope.

--	--
- f) Include for all scaffolding, motorized lifts & equipment to perform your scope.

--	--
- g) Provide warranties & installation guarantees upon completion of contract - One year warranty.

--	--
- h) Provide for all required protections and if applicable covering of any previous work competed by others.

--	--
- i) Provide all required shop drawings within 1 calendar week of contract issuance.

--	--
- j) Keep site clean from all garbage and debris caused by your scope of work.

--	--
- k) The contractor is responsible for daily removal of debris caused by its' scope of work.

--	--
- l) The contractor is responsible for all the temporary power required to complete its work (generator system).

--	--
- m) It is understood that the Sub-contractor will complete this scope of work in its entirety with its own forces. Any deviation, or sub contracting to other firms is prohibited without written approval from TAL-CO Building Innovations, prior to tender submission.

--	--
- n) Throughout the course of contract completion, it is the responsibility of the sub-contractor to address all deviation from this scope of work immediately. If not duly addressed, TAL-CO Building Innovations reserves the right to establish a fair and reasonable resolution to any/all outstanding issues.

--	--
- o) All extras & credits must be approved by the Project Manager prior to proceeding with the revised scope of work and the work must be verified by the site Superintendent.

--	--

It is the sub-contractors' responsibility to review, if necessary, all other project drawings or documents at our office located at 1341-2 Coker Street, Greely, Ontario, K4P 1A1. Additionally, all drawings and specifications can be found on our website at www.tal-co.com

--	--

It is the sub-contractors' responsibility to review and sign-off on the TAL-CO Health and Safety Plan prior to commencement of work. The sub-contractor has the responsibility to ensure all of their employees comply with the plan's requirements at all times.

--	--

Section #4 Site Specific Scope of Work Items

a) Supply and install all Formwork for footings, foundations, piers, pilasters, cassions, walls, and columns as per the DRAWINGS and SPECIFICATIONS

--	--

b) Include placement and required vibration of all concrete as per the DRAWINGS and SPECIFICATIONS

--	--

c) All sleeving pockets and depressions required for mechanical and electrical services as per the DRAWINGS and SPECIFICATIONS

--	--

d) Foundations will be frost walls to a minimum depth of 1800 mm as per the DRAWINGS and SPECIFICATIONS. Note insulation requirements if depths of 1800 mm cannot be achieved. Supply and install of this insulation by this trade.

--	--

e) Installation of anchor bolts as per the DRAWINGS and SPECIFICATIONS (supplied by others).

--	--

f) All lines and levels, surveying required for your work (TAL-CO to provide main axes and bench marks only).

--	--

g) Supply and installation of all waterstop, water bar, joint filler, etc., as per the DRAWINGS and SPECIFICATIONS

--	--

h) Installation of embedded items as per the DRAWINGS and SPECIFICATIONS

--	--

i) Supply and installation of insulation as required (due to footing depth) as per the DRAWINGS and SPECIFICATIONS

--	--

j) Allow for forming of step footings as per DRAWINGS and SPECIFICATIONS

--	--

- k) Supply and install all reinforcing steel pertaining to footings, foundation walls, etc. as per the DRAWINGS and SPECIFICATIONS

--	--
- l) Supply and install all asphalt impregnated fibreboard as per the DRAWINGS and SPECIFICATIONS

--	--
- m) Supply and install all slabs per the DRAWINGS and SPECIFICATIONS. This includes, Phase 1 and Phase 2 SOG, as well as the slab found in the Hose Tower.

--	--

Section #5 Work To Be Excluded From Your Scope of Work

- a) Waste removal containers

--	--
- b) Signage bases

--	--
- c) Light standard bases

--	--
- d) Concrete pump (if required)

--	--
- e) Supply of concrete

--	--
- f) Supply of anchor bolts

--	--

Section #6 Separate Prices To Be Excluded From Your Scope of Work

- a) Formwork of exterior slabs, pads, sidewalks

--	--

Section #7 Allowances To Be Included From Your Scope of Work

- a) N/A

--	--

Section #8 Phase Breakout Pricing

- a) Submit breakout pricing for Phase 1 and 2 scopes

--	--

Section #9 Appendix B - Bid Breakdown

- a) Refer to attached document.

--	--

END



B&GCO Prince of Wales
1463 Prince of Wales Drive
OTTAWA, ONTARIO, CANADA

Date: 14-Nov-17
Rev. #: 1
Rev. Date: 20-Dec-17

TENDER SUBMISSION - SUPPLEMENTARY INFORMATION

A. UNIT RATES

	DESCRIPTION	QTY	UNIT RATE	COST
1	SUPERVISOR RATE PER HOUR	N/A		N/A
2	LABOURER RATE PER HOUR	N/A		N/A
3	CONCRETE			
4	FORMS			
5				
6				
7				

B. SEPARATE PRICES EXCLUDED

	DESCRIPTION	QTY	UNIT RATE	COST
1				
2				
3				
4				

C. HEALTH & SAFETY PRE-QUALIFICATION

END OF DOCUMENT