

- 1- COORDINATE PASSAGE OF NEW SANITARY RISERS AND VENT STACK IN MECHANICAL SHAFT WITH NEW HVAC AIR DISTRIBUTION.
- 2- ALL EVAPORATORS PIPING, ELECTRICAL CABLE AND CONDENSATE PUMP TO BE INSTALLED INSIDE LINE SET COVER, FOR WALL MOUNTED UNITS
- 3- SEE DETAILS AND DIAGRAMS FOR ALL ACCESSORIES AND VALVES TO BE PROVIDED AND INSTALLED, DRAWINGS 210 AND ABOVE.
- 4- NO DOMESTIC WATER LINES, DRAIN LINE OR VENTS TO PASS IN THE OUTSIDE WALL, PIPING TO BE SURFACE MOUNTED, THIS INCLUDES MOST OF THE EXISTING WALLS IN THE EXISTING BUILDING.
- 5- CORES HAVE ALREADY BEEN MADE IN THE FLOOR AND WALLS FOR PAST FIT UP, REUSE IF POSSIBLE OTHERWISE TO BE CARPED OFF BY GENERAL CONTRACTOR AND NEW CORES TO BE MADE TO FIT WITH NEW SETUP.
- 6- FOR SANITARY PIPING (BRANCHES AND MAIN INCLUDING ALL VENTING) SEE DIAGRAM ON M-212 FOR SIZING.

1. END OF LINE FOR HOT WATER RECIRCULATION, INSTALL A BALANCING VALVE AND ADJUST TO 1.0gpm. INSTALL UNDER THE COUNTER TOP.
2. EXISTING CONCRETE BLOCK WALL, PROVIDE CORING THROUGH WALL FOR PASSAGE OF PIPING.
3. DRAIN CONDENSATE LINE VIA OPEN DRAIN.
4. SEE DETAILS FOR DRAINAGE OF DISHWASHER. PROVIDE ALL NECESSARY EQUIPMENTS FOR HOT WATER CONNECTION TO DISHWASHER FROM KITCHEN SINK SERVICE, COW ISOLATION VALVE.
5. CONDENSATE DRAIN LINE FROM ATTIC SPACE, SEND TO FUNNEL FLOOR DRAIN.


[illegible]

Architect

 **J.L. Richards**
ENGINEERS • ARCHITECTS • PLANNERS
www.jlrichards.ca

Structure

Sea



MAISON DE
DE LA FRANCOPHONIE D'OTTAWA
2720 RICHMOND ROAD, OTTAWA

MECHANICAL
PLUMBING
THIRD FLOOR NEW LAYOUT

Drawing n°

Revision



SCALE : 1/8"=1'-0"



SCALE : 1/8"=1'-0"



SCALE : 1/8"=1'-0"