

- 1- ALL BRANCH PIPING TO HEATING ELEMENT IS MIN. 3/4"Ø UNLESS OTHERWISE INDICATED ON DRAWINGS.
- 2- FOR EQUIPMENT DESCRIPTION, SEE SCHEDULE ON DRAWING M-310.
- 3- FOR HWS AND HWR BRANCH PIPING DIMENSIONS, SEE INSTALLATION DETAIL OF HEATING CABINETS ON DRAWING M-310 & 311.
- 4- WHEN HEATING EQUIPMENT IS INSTALLED IN SERIES, THE TEMPERATURE DROP ACROSS IS 20°F FOR THE WHOLE ARRANGEMENT.

1 EXPOSED PIPING TO BE INSULATED AS PER SPECIFICATIONS AND PAINTED TO MATCH WALL.



**PAGEAU
MOREL**
www.pageaumorel.com
Gatineau



J.L. Richards
ENGINEERS - ARCHITECTS - PLANNERS
www.jlrichards.ca

MAISON DE
DE LA FRANCOPHONIE D'OTTAWA
2720 RICHMOND ROAD, OTTAWA

Title

MECHANICAL
HEATING AND COOLING
GROUND FLOOR NEW LAYOUT

Drawn by :	B. TREMBLAY	Project n°:	7342-001-000
Design by :	B. TREMBLAY	Date :	2018-06-01
Verified by :	F. DIONNE	Scale :	1/8" = 1'-0"

Drawing n°	Revision
------------	----------

M-301	0
-------	---