



F L Y N N

ARCHITECT INC.

**CONTEMPLATED CHANGE NOTICE**

CCN NO: **10**  
 CONTRACTOR: **Mr. Pat Newton**  
**Talco Building Innovations Inc.**  
 4728 Bank Street  
 Ottawa ON K1T 3W7

CLIENT: **Mr. Ryan Firlotte**  
 Enterprise Holdings  
 Group Property Developemnt & Facilities Specialist  
 2300 Stevenage Dr.  
 Ottawa ON K1G 3W3

PROJECT NAME: **225 Huntmar**  
**Ottawa, Ontario**

PROJECT NO: 15-010  
 DATE: 2020, June 16

The following items are proposed changes to the contract documents previously issued for this project. Unless noted below, work is not to proceed until authorized by a change order. All material and workmanship are to be as described in the contract documents unless otherwise stated. Please submit an itemized quotation for changes to the tender price and/or to the project schedule, and within 5 calendar days of the date hereon.

REASON FOR CHANGE: **Clarification – Contractor Request**

1. Refer to attached Electrical CCN #4 from Antares Engineering dated June 16 2020.

END OF CCN

PER.....  
 Jason C. Flynn, OAA, MRAIC  
**Flynn Architect Inc.**  
 Email: j.flynn@flynnarchitect.com

DISTRIBUTION: as above





## CONTEPLATED CHANGE NOTICE

---

**CCN No:** Four (4) **Our Project Ref:** 15-610  
**Date:** 16 June 2020 **Your Project Ref:** Enterprise Rent-a-Car

---

**Project:** Enterprise Rent-a-Car  
225 Huntmar Drive  
Ottawa, Ontario

---

**Contractor:** TALCO Building Innovations Ltd.

---

*It is proposed to make the following change in the work. You are requested to quote a firm price for any revision to the contract amount arising from this change. No work should be undertaken on this change until a change order/written authorization has been signed and issued. Quotation to be submitted within 5 days of the date of this notice.*

---

Contemplated Work:

**Regarding: Break Room Receptacles.**

1. Move existing wall receptacle shown as DP-2 circuit #3 located in the break room from wall to under counter for new refrigerator.
2. Provide new break room counter top duplex receptacle GFI type c/w new dedicated circuit (DP-2 cir.#31) 120v, 1Ph, 60 Hz, 15A located in the middle of mill work.

----- End of CCN No. 4 -----

Per: Slavo. J. Samel  
ANTARES Engineering Group Inc.