

**1 FIRES**

- .1 Fires and burning of rubbish on site is not permitted.

**2 DISPOSAL OF WASTES**

- .1 Do not bury rubbish and waste materials on site.
- .2 Do not dispose of waste or volatile materials, such as mineral spirits, oil or paint thinner into waterways, storm or sanitary sewers.
- .3 Dispose of waste or volatile materials which could be hazardous to the health, in strict accordance with the requirements of the authorities having jurisdiction and in a manner which will protect construction personnel, visitors to the site and the public from all such hazards.

**3 DRAINAGE**

- .1 Provide temporary drainage and pumping as necessary to keep excavations and the site free from water.
- .2 Do not pump water containing suspended materials into waterways, sewer or drainage systems.
- .3 Control disposal or runoff of water containing suspended materials or other harmful substances in accordance with local authority requirements.

**4 POLLUTION CONTROL**

- .1 Control emissions from equipment and plant to conform to local authorities' emission requirements.
- .2 Prevent sandblasting and other extraneous materials from contaminating air beyond the application area by providing temporary enclosures.
- .3 Cover or wet down dry materials and rubbish to prevent blowing dust and debris. Provide dust control for temporary roads.

**END OF SECTION**